



4600 VICTORIA STREET NORTH
SHOREVIEW, MINNESOTA 55126
651.490.4600 | shoreviewmn.gov

Shoreview Winter Construction Specifications

When: Winter requirements for construction in Shoreview right-of-way start in the fall once the ambient temperature drops below freezing, until the temperature warms and stays above freezing in the spring. This is typically between November 1 and April 15, although the actual dates may vary based on weather conditions.

Pavement: No excavations will be allowed in paved road surfaces unless for emergency work. All pavement patches will be considered temporary. Cold Mix patches are not approved. Temporary patches are the responsibility of the permittee and must be monitored and maintained by the contractor until a permanent patch is made. The temporary patch must be completed no later than two(2) business days after the completion of the emergency repair.

Snow Clearing: Once the work in the roadway is completed any snow and ice in the work zone must be removed from the roadway before temporary traffic control devices are removed. Sidewalks and trails must be closed during any snow removal or construction activity in the boulevard and then cleared and reopened once the work is completed.

Bad Weather: During periods of inclement weather, or if inclement weather is imminent, no construction activity, except for emergency repairs, will be allowed within the roadway. This includes parked vehicles or equipment from the shoulder up to the curb. Freezing rain, sleet and snow create slippery road conditions and poor visibility. These conditions make work zones dangerous for both the traveling public and contractor personnel. During the winter season, daily permission may be needed from city staff as weather conditions change. Any construction work during the winter season must be approved by the County prior to the start of a project. The decision on whether or not a project can commence shall be at the discretion of the city.

Restoration: Temporary patches must be replaced with a permanent hot bituminous or concrete repair, to match existing pavement. All restoration, including replacing temporary patches, turf and trail damage, must be promptly restored in the spring.

Updated: 9/18/2026